

Field Evaluation of Pavement Quality Indicator as a Replacement for Nuclear Density Meter (Asphalt Paving)

Emile van Zyl

National Pavement Engineering Manager


Fulton Hogan Ltd


In situ Non-destructive Density Measurement

- NDM Problems:
 - Resourcing Constraints
 - Health and Safety (during transit)
 - Operational Ownership
 - Storage Constraints
 - Long term radiation exposure personnel
- NDM Superiority
 - Accuracy and Precision
 - Asphalt and Granular layer applications
 - Non-destructive
- Alternative Density Testing
 - Destructive test – Sand Replacement
 - Non-destructive – Pavement Quality Indicator
- Research Project Asphalt Densities
 - Advancements of PQI since 1990
 - Field trials of **PQI vs NDM vs Cores (2021/22)**
 - Plateau Field trials of **PQI vs NDM (2022/23)**



PQI Principle of Operation

- Main Function explained by a CIVIL ENGINEER
 - Density of material \propto dielectric constant
 - Emits electro-magnetic field through material
 - Receiver measures the amperage and impedance (resistance) is calculated accordingly.
 - **Impedance**  **Dielectric constant**
- Dielectric Constant Examples
 - Air – 1.0
 - Water 80
- Dielectric constant function of volume of the particular material type i.e. aggregate, bitumen and air.
- Asphalt layer thicknesses : 20 to 150 mm




PQI Accuracy and Precision

- **Surface Moisture**

- Water has the highest dielectric constant of 80 – gives false high compaction rating
- Roller water is acceptable in overseas standards as long as there is no pooling
- Will this be a problem when water cart is used to cool down the mat?

- **Temperature extremes**


- High temperatures affect dielectric constant of material
- Changes the reading the PQI gets
- Will this effect beginning of plateau tests?



High Accuracy
High Precision



Low Accuracy
High Precision



High Accuracy
Low Precision



Low Accuracy
Low Precision

PQI Functionality Aspects

- Lightweight and obtains readings in seconds
- Calibrated inside its housing unit
- Input project and mix design to store in the PQI
- Reduced ongoing costs due to no nuclear radiation

Control menu for mix design and project input





Field Trials Auckland -2021/22


Conducted PQI, NDM readings and extract cores at the some location, using the following procedure:

- Mark test position
- Record pavement & air temperatures, & time of each test
- Recorded calibration details for each device
- Ensured there was no water on or in the asphalt – asphalt surface must be absolutely dry before taking PQI readings
- Minimum of eight (8) test locations within each lot were identified & marked as per the random method in Clause 9.9.1 of NZTA M10: 2020
- For each location, the NDM test consisted of calculated average of two readings taken at 180-degree angles to each other (handle parallel to paving train), rotated about the centre point of the NDM gauge
- For each location, the PQI test consisted of the calculated average of 3 readings taken with the PQI rotated approximately 120 degrees after each reading
- All individual readings recorded
- Cores taken from the centre of the marked footprint
- Core densities determined in laboratory setting
- Plot PQI density versus core density, NDM density versus core density, & PQI density versus NDM density
- Linear regression including R-squared values & estimated regression functions.
- Assessed correlation between results of PQI density & core density, & between nuclear gauge density and core density



Results –Low Temperature (<40°C)




Results – Low Temperature (<math><40^{\circ}\text{C}</math>)



Results – High Temperature (40°C - 90°C)




Results – Higher Temp. (40°C-90°C)



Field Trials 21/22- Observations

- Status Quo - NDG
- PQI - Dielectric constant
 - Temperature
 - Moisture
- Accuracy Precision PQI Best @
 - $> 40\text{ }^{\circ}\text{C}$ and $< 90\text{ }^{\circ}\text{C}$
 - Moisture - NONE




Field Trials South Island -2022/23

Plateau Field Trial Canterbury:

- Mark test position;
- Record pavement & air temperatures, & time of each test;
- Recorded calibration details for each device (NDM and PQI);
 - Off-set for NDM set up prior to field measurements;
 - Off- set for PQI in some instances used;
- Plateau Density Process;
- Measure density after every 2 passes (NDM & PQI)
- End once compaction plateau achieved.


Nelson PQI Vs Core and PQI Vs NDM

- Similar to 21/22 Field trial



Plateau Field Trial Results –2022/23


Plateau Field Trials - Air Voids 100 mm WP (LPC 25/1/2023)



Additional Info:

- NDM Off-set +130 kg/m³
- PQI Off-set 0 kg/m³


Plateau Field Trials - Air Voids 100 mm WP (LPC 30/1/2023)



Additional Info:


- NDM Off-set +130 kg/m³
- PQI Off-set +45 kg/m³

Field Trial Results –2022/23 Nelson



Additional Info:

- PQI Off-set 71.7 kg/m³
- Cold temperatures 20-30°C



Additional Info:

- PQI Off-set 50 kg/m³
- Hot temperatures 70-115°C

Plateau Field Trials 22/23- Observations

- PQI Plateau Field Trial (Accuracy and Precision)
 - High Voids Inaccurate and Precision varies and reads consistently lower voids
 - Temperature effect on dielectric constant of asphalt materials hot mix paved at 160°C
 - Temperature specific off-set may solve the issue
- PTR rolling and surface regularity
 - Surface regularity during compaction process, knitted wheel loadings;
- Limitations to
- Direct comparison to NDM,



Going Forward

- Study findings:
 - Precision
 - Accuracy
 - Correlation observations
 - Shortcomings
 - Use of off-sets & Temperature bands
 - NDG vs PQI
- Compliance Suitability.....
- Process Control Tool – Aware of sensitivity



THANK YOU